

ILLEGIB

Approved For Release 2001/03/03 : CIA-RDP78T05439A000200290056-1

Approved For Release 2001/03/03 : CIA-RDP78T05439A000200290056-1

~~SECRET~~

NOFORN

(DOWNGRADING PROHIBITED)

25X1C

PIC/B-1001/61

March 1961


PHOTOGRAPHIC INTELLIGENCE BRIEF

DECLASS REVIEW by NIMA/DOD  
AIRFRAME PLANTS 126 AND 130,  
AND KOMSOMOLSK AIRFIELD  
USSR



MINICARD COPY

Published and Disseminated by  
CENTRAL INTELLIGENCE AGENCY  
PHOTOGRAPHIC INTELLIGENCE CENTER



~~SECRET~~

NOFORN

(DOWNGRADING PROHIBITED)

25X1C

SECRET

NOFORN

25X1C

S-8576

PIC/B-1001/61

Komsomolsk Airframe Plants 126 and 130 and the Komsomolsk Airfield are located in the northeastern outskirts of Komsomolsk, USSR, at 50-36N 137-05E. According to the Target Mosaic these plants are engaged in the production, overhaul and repair of jet fighter aircraft and are the only known producers of combat aircraft in the Soviet Far East.

Plant 126, located 500 yards southeast of Komsomolsk Airfield, occupies an area roughly 2,800 feet square and has a roof cover of approximately 984,000 square feet. Plant 130, located on the west side of the Komsomolsk Airfield, 1,000 yards northwest of Plant 126, occupies an area about 3,500 by 2,100 feet and has a roof cover of approximately 50,000 square feet. Both plants are rail served and fenced.

Komsomolsk Airfield is the test and flyaway field for aircraft produced by Plants 126 and 130. The runway, oriented north/south, measures approximately 6,400 feet by 260 feet. At the time of photography there were 98 FRESKOE, one probable CAB, two liaison-type, and one small unidentified aircraft on the field.

Major components of Komsomolsk Airframe Plants 126 and 130 are identified on the accompanying line drawings and described in the following tables of structures.




FIGURE 1. AIRFRAME PLANT 126, KOMSOMOLSK, USSR

- 1 -

MINICARE COPY

SECRET

NOFORN

25X1C

SECRET

NOFORN

25X1C

PIC/B-1001/61

25X1D

TABLE OF STRUCTURES, AIRFRAME PLANT 126

No.	Type of Building	Dimensions (ft)	Roof Cover (sq ft)	Floor Space (sq ft)
1	Warehouse	375 x 40	15,000	15,000
	Warehouse	200 x 40	8,000	8,000
	Warehouse	160 x 50	8,000	8,000
2	U/I building	75 x 30	2,250	2,250
3	Warehouse	130 x 30	3,900	3,900
	Warehouse	85 x 30	2,550	2,550
4	Warehouse	150 x 40	6,000	6,000
5	Receiving and shipping	175 x 150	26,250	26,250
6	Shop	250 x 60	15,000	15,000
7	Warehouse	150 x 30	4,500	4,500
	Warehouse	105 x 30	3,150	3,150
8	Garage	120 x 40	4,800	4,800
9	Control tower	40 x 30	1,200	3,600
10	Hangar	170 x 170	28,900	28,900
11	Guard barracks	115 x 40	4,600	4,600
12	Warehouse	160 x 30	4,800	4,800
	Warehouse	125 x 40	5,000	5,000
	Warehouse	110 x 40	4,400	4,400
13	Warehouse	600 x 65	39,000	39,000
14	Production shop	360 x 105	37,800	37,800
15	Warehouse	490 x 85	41,650	41,650
	Warehouse	215 x 20	4,300	4,300
16	Garage	150 x 40	6,000	6,000
17	Warehouse	320 x 30	9,600	9,600
18	Warehouse	560 x 40	22,400	22,400
19	Warehouse	60 x 30	1,800	1,800
20	Assembly shop	365 x 255	93,075	93,075
	Admin section	255 x 30	7,650	22,950
21	Locomotive shed	105 x 105	11,025	11,025
22	Transformer station	105 x 75	7,875	7,875
23	Steam plant	170 x 75	12,750	12,750
24	Warehouse	130 x 20	2,600	2,600
	Warehouse	150 x 40	6,000	6,000
25	Shop	195 x 85	16,575	16,575
26	Assembly shop	705 x 490	345,450	345,450
	Hangar section	400 x 135	54,000	54,000
27	Production shop	150 x 40	6,000	6,000
	Production shop	140 x 30	4,200	4,200
28	Production shop	200 x 110	22,000	22,000
29	Warehouse	170 x 40	6,800	6,800
30	Transformer station	55 x 20	1,100	1,100
31	Shop and warehouse	190 x 85	16,150	16,150
	Warehouse section	385 x 85	32,725	32,725
32	Guard barracks	65 x 40	2,600	2,600
33	Administration	55 x 40	3,400	3,400
	Wing	40 x 20	800	800
34	Administration	405 x 50	20,250	60,750
TOTAL			953,875	1,042,075

\* Three-story building. All others are single-story.

- 2 -

SECRET

NOFORN

25X1C

SECRET

NOFORN

DOWNGRADING PROHIBITED

25X1C

PIC/B-1001/61




FIGURE 2. AIRFRAME PLANTS 126 AND 130 AND KOMSOMOLSK AIRFIELD

25X1D

- 3 -

SECRET

NOFORN

DOWNGRADING PROHIBITED

25X1C

SECRET

NOFORN

(Downgrading Prohibited)

25X1C

PIC/B-1001/61




FIGURE 3. AIRFRAME PLANT 130, KOMSOMOLSK, USSR

TABLE OF STRUCTURES, AIRFRAME PLANT 130

No.	Type of Building	Dimensions (ft)		Roof Cover (sq ft)	Floor Space (sq ft)
1	Five warehouses	250 x 40		56,000	56,000
2	Four warehouses	170 x 55		37,400	37,400
	One warehouse	115 x 30		3,450	3,450
3	Steam plant	205 x 75		15,375	15,375
4	U/I building	65 x 55		3,575	3,575
	Wing	40 x 20		800	800
5	Shop	190 x 65		12,350	12,350
6	Two warehouses	110 x 50		11,000	11,000
	Eleven warehouses	110 x 25		30,250	30,250
7	Machine shop	430 x 170		73,100	73,100
8	Pattern shop	450 x 95		42,750	42,750
9	Maintenance shop	150 x 55		8,250	8,250
10	Main shop	250 x 60		16,500	16,500
	Wing	65 x 20		1,300	1,300
	Wing	40 x 30		1,200	1,200
	Wing	65 x 40		2,600	2,600
11	U/I building	170 x 30		5,100	5,100
12	Admin building	55 x 40		4,400	4,400
	Two wings	460 x 65		29,900	29,900
13	Assembly, roofed	460 x 245		-	112,700
	Assembly, no roof	150 x 50		7,500	7,500
14	Compressor building	65 x 40		2,600	2,600
15	U/I building	450 x 330		148,500	148,500
16	Assembly shop	450 x 45		20,250	60,750
	Admin section	620 x 110		272,800	272,800
17	Assembly shop	620 x 30		18,600	55,500
	Admin section	75 x 40		3,000	3,000
18	U/I building	65 x 30		1,950	1,950
19	U/I building	170 x 110		18,700	18,700
	Hangar				
TOTAL				849,500	1,039,900

\* Three-story building. All others are single-story.

- 4 -

25X1D

SECRET

NOFORN

(Downgrading Prohibited)

25X1C

25X1D

REFERENCES



MAPS or CHARTS

US Target Information Sheet, 0204-9998, 3 Dec 53 (S)  
SAC. US Air Target Chart, Series 25, Sheet 0204-9998-0-25A,  
1st ed, Dec 53, scale 1:25,000 (S)